

HARRISBURG MALL

HARRISBURG, PA

\$18.0M Feldman Properties Development

SPG3 Architects Design

DETAILS

New 16-screen cinema building over parking level

Partial demolition and reinforcement of portions of existing mall structure to allow new upper level connection to existing mall

Reinforcement of adjacent existing roof structure for snow drift loads resulting from new expansion

Floor level of cinema was designed with CIP concrete pan-joint construction to allow large spans, eliminate spray-on fireproofing & potential for future steel corrosion

Lateral bracing at the parking level was not required and numerous roof columns were economically transferred due to use of a concrete framing system

